

#### 2017 Facilities Engineering Seminar October 24-26, 2017

### New Marine Container Terminal at Haifa

(Hamifratz Port)

Bill Paparis, Project Manager, D. P.E.

# Preliminary Port Layout



# AAPA Aerial View of Existing Port





### Major Issues


- Moderately high level of earthquake accelerations, and associated potential for liquefaction of hydraulic fill and breakwater/revetment foundations
- Site exposed to waves
- Difficulty in obtaining adequate quantities of suitable sand from dredging for reclamation
- Environmentally sensitive location



### Maximum and Minimum Size Vessel Parameters

Parameter	Maximum Design Vessel (Quay 6)	Maximum Design Vessel (Quay 7)	Maximum Design Vessel (Quay 8)	Minimum Design Vessel
Vessel Type	Container Ship (Maersk EEE)	Container Ship (Post Panamax)	Container Ship (Panamax)	-
TEU Capacity	18,000	-	-	-
Deadweight Tonnage (dwt)	-	110,800	45,850	9,000
Length Overall (LOA), m	400	337	254	145
Beam, m	59.0	45.6	32.3	19.5
Loaded Draught, m	16.0	15.0	11.78	7.8
Loaded Displacement, tonnes	240,000	147,000	62,750	14,247

# 3D Model Testing of Port Layout



# AAPAReal Time NavigationSimulation – Emma Maersk





### Seismic Study

- Developed seismotectonic model taking into account regional tectonic setting, historical seismicity and mapped faults, including fault slip rates.
- Most important source is the Carmel Fault, located between 1.7 km and 2.9 km from the site.
- Model also includes the Dead Sea Transform Fault and Cyprus Trench, as well as more local sources such as the Levant Fault and the Gilboa Fault.
- Model was input into a computer program and Probabilistic Seismic Hazard Assessments were conducted for return periods of 72, 475, 975, and 2,475 years.



### Three Levels of Seismic Design


- Contingency Level (10% Probability of Exceedance in 50 Years): Peak Ground Acceleration = 0.38 g (M=6.5-7.0)
- Operating Level (50% Probability of Exceedance in 50 Years): Peak Ground Acceleration = 0.12 g (M=4.5-5.0)
- Contingency Level for D&H Cargo (2% Probability of Exceedance in 50 Years): Peak Ground Acceleration = 0.86 g



- Main Breakwater and Lee Breakwater were considered to be PIANC Grade A (primary) structures, so that minimal damage is expected in an OLE, while the damage in a CLE is controlled and repairable, and the structure is to remain serviceable
- For the CLE the stability of the structures was assessed in terms of the magnitude of the deformation
- Maximum permissible deformation under CLE  $\approx$  1.0 m
- Maximum side slopes were determined to be 1V to 2H



### Final Port Layout




# AAPA

### 3D Physical Model Testing of Main Breakwater Extension




## AAPA Typical Section Along Trunk of Main Breakwater Extension






### Typical East Breakwater Cross Section



### Seismic OLE Slope Stability Analysis of East Revetment Caisson – 9.6 m Clay Removal






### Seismic (CLE) Displacements of East Revetment Caisson


Displacements from FLAC Analyses for the CLE Condition		Allowable Displacements As Defined in PIANC Document		
Displacements at the End of Earthquake Shaking	Magnitude of Displacements (Approx.)	Degree II Damage Level (for CLE Condition)	Degree I Damage Level (for OLE Condition)	
Horizontal Displacement at Caisson Seaward Face	15 cm - 20 cm	30 cm to 90 cm	30 cm	
Settlement at Caisson Toe	12 cm	N/A	N/A	
Settlement at Caisson Heel	2 cm	N/A	N/A	
Titling of Caisson Seaward Facing	0.25 degree	3 to 5 degree	Less than 3 degree	
Horizontal Displacement of Backfill Directly Behind Caisson	10 cm	N/A	N/A	
Settlement of Backfill Directly Behind Caisson	30 cm	N/A	Less than 30 to 70 cm	

# AAPA

### Geological Profile Along Quay 6




# Quay 6 Typical Cross Section



Δ

# AAPALateral Motion of Piles and SoilMass at Quay 6 Due to Shaking




#### Notes:

(1) The black lines represent the pre-earthquake locations of the piles, bulkhead, and deadman; and the red lines represent their post-earthquake locations.

(2) The green lines represent the deformed soil mesh.

# AAPA

### Dredging Plan - Harbor






## Dredging Evaluation for EIA

- Evaluated preferred 70% (full) loading scenario and it was determined to be unacceptable from an environmental standpoint due to high levels of spillage
- Developed dredging plans for 45% parallel loading scenario and these were used to evaluate acceptability from environmental standpoint
- Based on this, loading of dredgers will have to be limited so as not to exceed environmental thresholds, thus resulting in higher fines content for reclamation fill



### Ground Improvement (GI)




22


### AAPA Construction of Lee Revetment



### AAPA Casting of Concrete Caisson



# AAPA Completed Concrete Caisson



### **AAPA** *Driving Main Sheet Pile Wall at Quay 6*



# **AAPA** *Ground Improvement*



### **Construction of Main Breakwater** Extension



### **Construction of Main BW** Extension Roundhead



#### AAPA View of Quay 7, Quay 6, and Reclamation Area





#### 2017 Facilities Engineering Seminar October 24-26, 2017


### New Marine Container Terminal at Ashdod

(Hadarom Port)

Bill Paparis, Project Manager, D. P.E.



### Port Layout





### Major Issues


- Site directly exposed to high waves from Mediterranean Sea
- Moderate levels of earthquake accelerations, and associated potential for liquefaction of hydraulic fill and poor soils underlying breakwater foundations
- Potential settlement of reclamation area and breakwaters due to deep clay layers
- Concern over increased downtime in existing port due to construction staging



### Maximum and Minimum Size Vessel Parameters

Parameter	Maximum Design Vessel (Quay 27)	Maximum Design Vessel (Quay 28)	Minimum Design Vessel
Vessel Type	Container Ship (Maersk EEE)	Container Ship (Panamax)	-
TEU Capacity	18,000	4,000	600
Loaded Displacement, tonnes	240,000	75,000	10,000
Length Overall (LOA), m	400	270	125
Beam, m	59.0	32.2	20
Loaded Draught, m	16.0	12.0	7.6

### AAPA Wave Agitation Plot for North-West Wave Direction




35

### AAPA Overview of the Ashdod Port Model in Large Area Basin (CHC, Canada)



## AAPA Plan of Main Breakwater Extension




37



### Main Design Issues for Main Breakwater Extension

- Maximum significant wave height of 8.3 m
- Anticipated long-term settlement
- Potential liquefaction of underlying soils








#### NOTES

1. ALL UNITS IN METERS UNLESS OTHERWISE NOTED.

2. COORDINATE GRID BASED ON NEW ISRAEL GRID.

3. ALL ELEVATIONS BASED ON ISRAELI LAND SURVEY DATUM (ILSD).

- THE CROSS SECTIONS ARE BASED ON INTERPOLATED DATA FROM THE SOIL INVESTIGATION BY GEMS (2009/2010). THE BOREHOLES ARE PROJECTED PERPENDICULAR TO THE SECTION.
- THESE DRAWINGS ARE SHOWING INFORMATION AS GATHERED DURING THE SOLL INVESTIGATION BY GENS (2009/2010). ALL SOLL INVESTIGATION RESULT: (PREVOUS INVESTIGATIONS AS WELL) ARE AVAILABLE FOR THE CONTRACTOR'S REVIEW.






- Slope stability analyses were carried out for three loading conditions:(1) static; (2) pseudo static for contingency level earthquake conditions; and (3) post-seismic static loading using residual undrained shear strengths.
- The loose silty sand was determined to be liquefiable (based on a PGA = 0.12 g and M = 7.5), while the silt was determined to be susceptible to strength reduction.
- Further analyses were then carried out assuming that the silty sand is: (1) replaced; and (2) improved, and the maximum earthquake induced displacements were on the order of 60-80 cm, which is considered acceptable for this type of structure, as it can accommodate lateral deformation.
- Stone columns with an area replacement ratio of 13% were implemented to improve the silty sand.



#### Section of Main Breakwater Extension At Chainage 100



CHAINAGE 100

#### NOTES

- 1. ALL UNITS IN METERS UNLESS OTHERWISE NOTED.
- 2. COORDINATE GRID BASED ON NEW ISRAEL GRID.
- 3. ALL ELEVATIONS BASED ON ISRAELI LAND SURVEY DATUM (ILSD).
- ANTIFER CUBES SHOWN ARE ILLUSTRATIVE. PLACING OF UNITS SHALL BE IN ACCORDANCE WITH SPECIFICATIONS.
- 5. FOR CROWN WALL DETAILS SEE DWG NOS. C-261 THRU C-0264
- 6. FOR CONSTRUCTION TDLERANCES SEE DWG NO. C-




#### 2D Stability Testing of Main Breakwater Extension (H.R. Wallingford, UK)



#### **AAPA** *3D Stability Testing of Lee Breakwater Roundhead (H.R. Wallingford, UK)*



#### AAPA Section of Lee Breakwater at Chainage 400




CHAINAGE 400 SCALE 1: 150


#### NOTES

- 1. ALL UNITS IN METERS UNLESS OTHERWISE NOTED
- 2. ALL ELEVATIONS BASED ON ISRAELI LAND SURVEY DATUM (ILSD).
- ANTIFER CUBES SHOWN ARE ILLUSTRATIVE. PLACING OF UNITS SHALL BE IN ACCORDANCE WITH SPECIFICATIONS.
- 4. FOR CONSTRUCTION TOLERANCES SEE DWG NO. XYZ.

#### AAPA Section at Roundhead of Lee Breakwater



# **Geological Profile Along Quay 27**





Upper Clay 3 UC3

Middle Clay MC

Middle Kurkar MK

Lower Clay LC

Upper Kurkar UK

Lower Kurkar LK Deep Cloy DC

Deep Kurkar (Up) DKU


Deep Dark Clay DDC

Deep Kurkar (Down) DKD

Deep Silty Sand DSS

Deep Siltstone DST

- ALL ELEVATIONS BASED ON ISRAELI LAND SURVEY DATUM (ILSD). 3 THE CROSS SECTIONS ARE BASED ON INTERPOLATED DATA FROM SOIL INVESTIGATION BY GEMS (2009/2010). THE BOREHOLES PROJECTED PERPENDICULAR TO THE SECTION. THE
- 5. THESE DRAWINGS ARE SHOWING INFORMATION AS GATHERED DURING THE SOIL INVESTIGATION BY GEMS (2009/2010). ALL SOIL INVESTIGATION RESULTS (PREVIOUS INVESTIGATIONS AS WELL) ARE AVAILABLE FOR THE CONTRACTOR'S REVIEW.






#### Quay 27 – Crane Loads

		Waterside	Landside	
Maximum Wheel Load	tonnes/wheel	160	130	
Maximum Load on Crane Beam	tonnes/m	130	110	
Maximum Lateral Force on WS or LS Rail	tonnes	15% of Vertical Load	15% of Vertical Load	
Anchor Pin Loads (Storm)	tonnes	200	200	
Tie-Down Loads	tonnes/corner	220	220	



#### Quay 27 – Typical Section




#### NOTES

1. ALL UNITS IN METERS UNLESS OTHERWISE NOTED.


2. ALL ELEVATIONS BASED ON ISRAELI LAND SURVEY DATU



#### Quay 28 – Typical Section




#### AAPA Instantaneous Steady State Wave Disturbance Plot for Construction Phase




50



### Wave Heights at Existing Quays 23, 22, and 21





# AAPA Front View of Quay 28 Model Testing





- Due to the questionable quality and uncertainty of the original geotechnical data, settlement calculations were based on the assumption that all clay layers were normally consolidated.
- Based on the original 2009/2010 boring logs, without any ground treatment, the maximum post-construction settlements at the western area of the site were estimated to be up to 70 cm.
- Analyses indicated that a wick drain program in combination with 2 m of surcharge would be effective in reducing the post-construction settlements to 35 cm or less.
- An additional geotechnical investigation was performed during construction to attempt to minimize the uncertainty.



### General Subsurface Stratigraphy

Sti	rata #	Strata LEGEND	Strata ID					
	1		UMS	Upper Medium Sand				
	2		MS	Medium Sand				
	3		ULS	Upper Loose Sand				
	4		SL	Silt (not seen in the reclamation area)				
	5		UDS	Upper Dense Sand				
	6		UC UC1/UC2/UC3	Upper Clay				
	7		UK	Upper Kurkar				
	8	1/1	MC	Middle Clay				
	9		MK	Middle Kurkar				
	10	111	LC	Lower Clay				
	11		LK	Lower Kurkar				
	12	+	DC	Deep Clay				
	13	O S	рки	Deep Kurkar (Up)				
	14	$\sim$	DDC	Deep Dark Clay				

### AAPA Time-Dependent Settlement Parameters (Based on Additional Geotechnical Investigation)

Unit	γ' (kN/m³)	PI	Cc	Cr	e <sub>0</sub>	Ca	C <sub>v</sub> (m²/year)	OCR top to bot (PCPTs)	OCR top to bot (triaxial)
UC	9	30	0.295	0.045	0.898	0.004	1.5	2.9 to 1.5	2 to 1.6
МС	8	36	0.45	0.057	1.183	0.0054	0.75	1.6 to 1.2	1.3
LC	9.4	30	0.247	0.025	0.769	0.0036	1	2.1 to 1.3	1.5
DC	9.7	23	0.248	0.025	0.774	0.006	0.75	1.6 to 1.5	1.5



# *Key Post-Construction Settlement and Differential Settlement Values*

Differential settlement between waterside and landside rails at Quay 27:

- 10 years after the completion of construction: 5.8 cm
- 20 years after the completion of construction: 7.4 cm
- 50 years after the completion of construction: 8.4 cm

Maximum settlement within the reclamation area:

- 10 years after the completion of construction: 15.4 cm
- 20 years after the completion of construction: 18.6 cm
- 50 years after the completion of construction: 22.2 cm

# AAPA Lee Breakwater and Temporary Retaining Structure Construction




## AAPA Lee Breakwater & Reclamation Area Construction





#### **Quay 28 Construction**





#### **Quay 27 Construction**





#### **Quay 27 Construction**



# AAPA Main Breakwater Extension Construction









